



NOMINAL BORE	TOTAL LENGTH (L) (+/-5mm)	BELLOWS	
		CORRS	A
mm			
20	880	28+28+28	185
25	880	28+28+28	185
32	920	28+28+28	200
40	920	26+26+26	200
50	920	26+26+26	200

CONSTRUCTION

ITEM	PARTS	MATERIAL
1	BELLOWS	SST304 (2 PLY)
2	TUBE	CARBON STEEL
3	GUSSET	CARBON STEEL
4	TIE RODS	CARBON STEEL
5	INNER SLEEVE	SST304
6	EXTERNAL SHROUD	CARBON STEEL

STANDARD FINISH

FLANGES / GUSSETS : GALVO PAINT
 CONTROL ROD : ZINC PLATED
 & HARDWARE

Model - SSEJ-250T-SG-ES
THREADED END - SCHEDULE 40 PIPE

WORKING PRESSURE : 16 bar
 WORKING TEMPERATURE : -50°C to +450°C
 AXIAL MOVEMENT : + / - 100mm

WARNING : - Control units must be used to protect this part from excessive movement if piping is not properly anchored.